

## Lab - Certificate Authority Stores

### Objectives

**Part 1: Certificates Trusted by Your Browser**

**Part 2: Checking for Man-In-Middle**

### Background / Scenario

As the web evolved, so did the need for security. HTTPS (where the 'S' stands for security) along with the concept of a Certificate Authority was introduced by Netscape back in 1994 and is still used today. In this lab, you will:

- = List all the certificates trusted by your browser (completed on your computer)
- = Use hashes to detect if your internet connection is being intercepted (completed in the Security Workstation virtual machine)

### Required Resources

- = Security Workstation virtual machine
- = Internet access

### Instructions

#### Part 1: Certificates Trusted by Your Browser

HTTPS relies on a third-party entity for validation. Known as Certification Authority (CA), this third-party entity verifies if a domain name really belongs to the organization claiming its ownership. If the verification checks, the CA creates a digitally signed certificate containing an information about the organization, including its public key.

The entire system is based on the fact that web browsers and operating systems ship with a list of CAs they trust. Any certificates signed by any of the CAs in the list will be seen by the browser as legitimate and be automatically trusted. To make the system more secure and more scalable, CAs often spread the task of creating and signing certificates among many child CAs. The parent CA is known as the Root CA. If a browser trusts a Root CA, it also trusts all of its children CAs.

**Note:** While the certificate stores are similar across browsers, this lab focuses on **Chrome 81** and **Firefox 75**. The menu and graphics may be different for other versions of the web browser.

Follow the steps to display the CA store in your browser:

#### Step 1: Display the Root Certificates in Chrome.


You can do this step on your local machine or use FireFox in the Security Workstation VM. If you use Firefox, proceed to Step 2. If you use a browser other than Chrome or Firefox, search the internet for the steps to display your root certificates.

**Note:** The menu and graphics may be different for other versions of the Chrome browser.


- Open the Chrome web browser on your PC.

## Lab - Certificate Authority Stores

- b. Click the three-dot icon on the far right of the address bar to display Chrome's options. Click **Settings**.




- c. Scroll down to **Privacy and security** and click **Security**.
- d. Scroll down and select **Manage certificates**.
- e. In the Certificate window, select **Trusted Root Certification Authorities** tab to show all certificates and certificate authorities trusted by Chrome.




### Step 2: Display the Certificates in the CA Store in Firefox.

**Note:** The menu and graphics may be different for other versions of the Firefox browser and between different operating systems. **Firefox 94** on the Security Workstation VM is shown in this step.

- a. Open Firefox and click the Menu icon. The **Menu** icon is located on the far right of the Firefox window, next to the address bar. Click **Settings**.



- b. Click **Privacy & Security** in the left panel.
- c. Scroll down to the Security section and click **View Certificates**.
- d. A window opens that shows the certificates and certification authorities trusted by Firefox.



### Part 2: Checking for Man-In-Middle

This part is completed using the Security Workstation VM.

A common use for hashes is to verify data integrity, but they can also be used to detect HTTPS man-in-the-middle attacks.

To protect user data, more and more websites are switching to encrypted traffic. Known as HTTPS, sites use protocols such as TLS/SSL to encrypt user traffic from end to end. After the traffic is properly encrypted, it is very difficult for any party other than the user and the site in question to see the contents of the encrypted message. This is good for the users, but it creates a problem for organizations that want to look into that traffic. Companies and organizations often choose to peek into employee-generated traffic for monitoring purposes. They needed to be able to look into TLS/SSL-encrypted traffic. This is done by using an HTTPS proxy.

Web browsers trust the identity of a visited web site if the certificate presented by that web site is signed by one of the CAs installed in the browser's certificate store. To be able to peek into its users' TLS/SSL-encrypted traffic, a company or organization simply adds another CA into the user's browser list of installed CA.

Consider the following scenario: Company X hires a new employee and provides him with a new company laptop. Before handing over the laptop, the company IT department installs all the software necessary for the work. Among the software and packages that are installed, the IT department also includes one extra CA to the list of trusted CAs. This extra CA points to a company-controlled computer known as the HTTPS proxy. Because the company controls traffic patterns, the HTTPS proxy can be placed in the middle of any connection. It works like this:

1. The user attempts to establish a secure connection to HTTPS web site H, hosted on the internet. H can be any HTTPS site: a bank, online store, email server, etc.
2. Because the company controls traffic patterns, it makes it so that all user traffic must traverse the HTTPS proxy. The HTTPS proxy then *impersonates* web site H and presents a self-signed certificate to prove it is H. The HTTPS proxy essentially says "Hi there, I am HTTPS site H. Here's my certificate. It's has been signed by... myself."
3. Because the presented certificate is signed by one of the CAs included in the laptop's CA store (remember, it was added by IT), the web browser mistakenly believes it is indeed communicating with H. Notice that, had the extra CA not been added to the CA store, the laptop would not trust the certificate and immediately realize that someone else was trying to *impersonate* H.

4. The laptop trusts the connection and establishes a secure channel with the HTTPS proxy, mistakenly believing it is communicating securely with H.
5. The HTTPS proxy now establishes a second secure connection to H, the web site the user was trying to access from the beginning.
6. The HTTPS proxy is now the end point of two separate secure connections; one established with the user and another established with H. Because the HTTPS is the end point of both connections, it can now decrypt traffic from both connections.
7. The HTTPS proxy can now receive TLS/SSL-encrypted user traffic destined to H, decrypt it, inspect it, re-encrypt it using TLS/SSL and send it to H. When H responds, the HTTPS proxy reverses the process before forwarding the traffic to the user.

Notice that process is mostly transparent to the user, who sees the connection as TLS/SSL-encrypted (green marks on the browser). While the connection is secure (TLS/SSL-encrypted), it has been established to a spurious web site.

Even though their presence is mostly transparent to the user, TLS proxies can be easily detected with the help of hashes. Considering the example above, because the HTTPS proxy has no access to the site H private keys, the certificate it presents to the user is different than the certificate presented by H. Included in every certificate is a value known as a *fingerprint*. Essentially a hash calculated and signed by the certificate issuer, the fingerprint acts as a unique summary of all the contents of the certificate. If as much as one letter of the certificate is modified, the fingerprint will yield a completely different value when calculated. Because of this property, fingerprints are used to quickly compare certificates. Returning to the example above, the user can request H's certificate and compare the fingerprint included in it with the one provided when the connection to the web site H was established. If the fingerprints match, the connection is indeed established to H. If the fingerprints do not match, the connection has been established to some other end point.

Follow the steps below to assess if there's a HTTPS proxy in your connection.

### Step 1: Gathering the correct and unmodified certificate fingerprint.

The first step is to gather a few site fingerprints. This is important because these will be used for comparison later. The table below contains a few site certificate fingerprints from popular sites.

**Note:** The SHA-1 fingerprints shown in Table 1 may no longer be valid as organizations regularly renew their certificates. A fingerprint is also called a thumbprint in Windows-based machines.

**Table 1 - Popular Sites and Their SHA-1 Certificate Fingerprints**

| Site                                                     | Domains Covered By Certificate                         | Certificate SHA-1 Fingerprint (as of May 2020)              |
|----------------------------------------------------------|--------------------------------------------------------|-------------------------------------------------------------|
| <a href="http://www.cisco.com">www.cisco.com</a>         | <a href="http://www.cisco.com">www.cisco.com</a>       | E2:BD:0B:58:C6:B4:FF:91:D6:23:AB:44:0D:8F:64:76:29:4E:30:0B |
| <a href="http://www.facebook.com">www.facebook.com</a>   | *.facebook.com                                         | BB:E7:A0:97:C7:92:B2:2D:00:38:12:69:E4:64:E9:04:96:4B:C7:41 |
| <a href="http://www.wikipedia.org">www.wikipedia.org</a> | *.wikipedia.org                                        | A8:F9:F7:79:BE:DB:3E:EB:59:F0:1D:A6:34:08:A1:64:5D:28:48:44 |
| <a href="http://twitter.com">twitter.com</a>             | twitter.com                                            | 73:33:BB:96:1D:DB:9C:0C:4F:E5:1C:FF:68:26:CF:5E:3F:50:AB:96 |
| <a href="http://www.linkedin.com">www.linkedin.com</a>   | <a href="http://www.linkedin.com">www.linkedin.com</a> | 04:BC:C5:09:DD:AE:99:40:7E:99:A5:65:32:68:EC:5D:2D:D7:5A:19 |

What are the fingerprints? Why are they important?

Who calculates fingerprints? How to find them?

### Step 2: Gather the certificate fingerprint in use by the Security Workstation VM.

Now that we have the actual fingerprints, it is time to fetch fingerprints from a local host and compare the values. If the fingerprints do not match, the certificate in use does NOT belong to the HTTPS site being verified, which means there's an HTTPS proxy in between the host computer and the HTTPS site being verified. Matching fingerprints means no HTTPS proxy is in place.

- a. Use the three piped commands below to fetch the fingerprint for Cisco.com. The line below uses OpenSSL to connect to cisco.com on port 443 (HTTPS), request the certificate and store it on a text file named **cisco.pem**. The output is also shown for context.

```
[analyst@secOps ~]$ echo -n | openssl s_client -connect cisco.com:443 | sed
-ne '/-BEGIN CERTIFICATE-/,/-END CERTIFICATE-/p' > ./cisco.pem
depth=2 C = BM, O = QuoVadis Limited, CN = QuoVadis Root CA 2
verify return:1
depth=1 C = US, O = HydrantID (Avalanche Cloud Corporation), CN = HydrantID SSL ICA G2
verify return:1
depth=0 C = US, ST = CA, L = San Jose, O = "Cisco Systems, Inc.", CN = www.cisco.com
verify return:1
DONE
```

- b. Optionally, use the **cat** command to list the contents of the fetched certificate and stored in the **cisco.pem** text file:

```
[analyst@secOps ~]$ cat cisco.pem
-----BEGIN CERTIFICATE-----
MIIGlzCCBL+gAwIBAgIUkBO9xTQoMemc9zFHNkdMW+SgFO4wDQYJKoZIhvcNAQEL
BQAwXjELMAkGA1UEBhMCVVMxMDAuBgNVBAoTJ0h5ZHJhbnRJRCAoQXZhbGFuY2hl
IENSb3VkeiENvcnBvcnF0aW9uKTEuMBSGA1UEAxMUSHlkcmFudE1EIFNTTCBJQ0Eg
RzIwHhcNMjcxMjA3MjIyODU1WhcNMjcxMjA3MjIyODU1WjBjMQswCQYDVQQGEwJV
UzELMAkGA1UECAwCQ0ExETAPBgNVBAMCFNhhbiBkb3NlMRwwGgYDVQQKBDBDaXNj
byBTeXN0ZWl1zLCBjb2MUMRYwFAYDVQQDDA13d3cuY2l1zY28uY29tMIIBIjANBgkq
yvo6dWpJdSircYy8HG0nz4+936+2waIVf1BBQXZUjNVuws74Z/eLIpl2c6tANmE0
q1i7fiWgItjDQ8rfjeX0oto6rvp8AXPjPY6X7PT1ulfhkLYnxqXHPETRwr815COO
MDEh95cRxATXNALWAwLcBT7lDmrGron6rW6hDtuUPPG/rjZeZbNww5p/nT3EXX2L
Rh+m0R4j/tuvy/77YRWyp/VzhmSLrvZEYiVjM2MgCXBvqR+aQ9zWJkw+CAm5Z414
Eiv5RLctegYuBUMGTH1a19r5cuzfwEg2mNkx14I/mtDro2kDAv7bcTm8T1LsZAO/
1bWvudsrtA8jksw+1WGAEd9bHi3ZpJPYedlL
-----END CERTIFICATE-----
[analyst@secOps ~]$
```

- c. Now that the certificate is saved in the **cisco.pem** text file, use the command below to extract and display its fingerprint:

```
[analyst@secOps ~]$ openssl x509 -noout -in cisco.pem -fingerprint -sha1
SHA1 Fingerprint=64:19:CA:40:E2:1B:3F:92:29:21:A9:CE:60:7D:C9:0C:39:B5:71:3E
[analyst@secOps ~]$
```

**Note:** Your fingerprint value may be different for two reasons. First, you may be using a different operating system than the Security Workstation VM. Second, certificates are regularly refreshed changing the fingerprint value.

What hash algorithm was used by OpenSSL to calculate the fingerprint? **ANSWER: Secure Hash Algorithm 1 (SHA1)**

Why was that specific algorithm chosen? Does it matter? **Answer: This Hash algorithm was used specifically because it creates a unique fixed sized digital fingerprint.**

### Step 3: Compare the Fingerprints

Use Table 1 to compare the certificate fingerprint acquired directly from the Cisco HTTPS site with the one acquired from within your network. Recall, fingerprints may change over time.

Do the fingerprints match? **ANSWER: No, the fingerprints do not match.**

What does it mean? **Answer: This means that the data is not identical to the original.**

Is this method 100% foolproof? **Answer: No, this method is not 100% foolproof.**

### Part 3: Challenges (Optional)

- a. Check the fingerprints for the sites shown in Table-1 but using your web browser's GUI.


**Hints:** Find a way to display the fingerprint through the browser's GUI. Remember: Google is useful in this exercise, and Windows often refers to the Fingerprint as **Thumbprint**.

- b. Use the OpenSSL (Part 2, Steps 1 through 3) to check all the fingerprints listed in Table-1

### Reflection Question

What would be necessary for the HTTPS proxy to work?

## Lab - Certificate Authority Stores





File
Machine
View
Input
Devices
Help

File Edit View Search Terminal Help

```

MQswcQYDVQGEwJVUzESMBAGA1UEChMJSWRlb1RydXN0MS4wLAYDVQQLYyVieWRy
YW50SUQgVHJ1c3RlZCB0ZXJ0aWZpY2F0ZSB7ZXJ2aWNlMR8wHQYDVQDEExZiEwRy
YW50SUQgU2VydMvYiENBIE8xMB4XD0TI1MDgyMjA0MjIwN1oXDTI2MDkyMTA0MjEw
N1owajELMAkGA1UEBhMCVVMxEzARBgNVBAGTCkNhbgGmb3JuaWExETAPBgNVBACT
CFNhb1Bkb3NlMRswGQYDVQKExJDaxNjbyBTeXN0ZW1zIEluYy4xZjAUBGVBAMT
DXd3dy5jaXNjby5jb20wggEiMA0GCSqGSIb3DQEBAAQAAIBDwAwggEKaoIBAQC5
ZmHLURk41GSEtQzPuoloq7hU+DQNVAE94JUNw8Av9wjcRNLJFE7/Y3fFRiWnms83
kera8Q/cG+mYCUKk+2KDKc+MV28T1zQvTiAgLMx/FWpMNO2lwWAut2tWoJd95Ex2
EtBBQhD6d1n85geQfNl9vSGE6eIz04PfwKtq2hV7yHbVESVLR+ZUCv5nR9ZXLZb6
BiIOJBHmcXf80zy0gCymPiJg9smNLHJ5mT5M9q7KB7YH9GX8BNVi2qGn4eDX19Y9
IuVu1FX5403YGTd4qrD+hLv9WQ0CJg3vABWAPEgaOKm/BLNyeLU088L1ftfl2QBc
Dx+aPYES0T27PiK2xtTvAgMBAAGjggQqMIEJjA0BgNVHQ8BAf8EBAMCBaAwgYUG
CCsGAQUFBwEBBHKwdzAwBggrBgEFBQcwAYYkaHR0cDovL2NvbW1lcmNpYwWub2Nz
cC5pZGVudHJ1c3QuY29tMEMGCCsGAQUFBzAchjdodHRwOi8vdmFsaWRhGlvbi5p
ZGVudHJ1c3QuY29tL2NlcnRlZ2h5ZjHbnRzZGNhTzEuY29tZjB8GA1UdIwQYMBAA
FIm4m7ae7fuwxr07GdOPKOSnS35MCEGA1UdIAQaMBgwCAYGZ4EMAQICMAwGCMCG
SAGG+S8ABgMwRgYDVR0fBD8wPTA7oDmgN4Y1aHR0cDovL2ZhbGlkYXRpb24uawRl
bnRydXN0LmNvbS9jcmwvaHlkcmludGlvY2FvMS5jcmmwggE9BgNVHREEGgE0MIIIB
MIJY2lZy28uY29tg93d3cuY2lZy28uY29tg93d3cxLmNpc2NvLmNvbYiOd3d3
Mi5jaXNjby5jb22CDnd3dzMuY2lZy28uY29tghB3d3ctMDYuY2lZy28uY29tghB3
d3ctMDIuY2lZy28uY29tghF3d3ctcnRwLmNpc2NvLmNvbYISd3d3MS1zcziUy2lZ
Y28uY29tghJ3d3cyLXNzMS5jaXNjby5jb22CEND3dzMtc3MxLmNpc2NvLmNvbYIS
d3d3My1zcziUy2lZy28uY29tghR3d3cuc3RhdGlvLWNPc2NvLmNvbYIVcmVkaXJl
Y3QtbmMuY2lZy28uY29tghZ3aXNjby1pbWFnZXMuY2lZy28uY29tghh3d3cubWVk
aWFmaWxlcY1jaXNjby5jb20wHQYDVRO0BBYEFDFP00TyhQAYI0Gmxk5JIsUWLQqE
MB0GA1UdJQKQMBQGCCsGAQUFBwMBBggrBgEFBQcDAjCCAX8GCSiGAQ0B1nkCBAIE
ggFvBIIbawFpAHYA1219ENG9XfCx+lf1wC/+YlJM1pl4dCzAXMXwMjFaXCAAAGY
0AM1RQAABAMARzBFAiEASOMi4psAyp2o+NI6c0KxSLjM+havNi9P6TiXdlbtbTG8C
ICY6jYG0a+Wk1zXJdi3RH6TjRrETAp78L5GsFjVvh3vNAHYA2AlV05Rpev/IFhlv
LE+Fq7D4/F6HVSYPfDeucrTFsXQAAAGY0AM1ewAABAMARzBFAiBqW6JMTGGWNZ3i
+etSS2yfCwwIUNcssom/gG/1HgNusQIhANLjchov5HqC9knPZimMmJ4K01ipIe8s
Y66VvJGyvuCPAHcAyzj3FYl8hKFEX1vB3fvJbvKawc1HCmkFhbDLFMMUW0cAAAGY
0AM1YgAABAMASDBGAiEALuzTTvYrx4TV798tT8dycz+Hs5LUDTbCcLFRsYc5IRwC
IQDe881kW5T0of8Ig2hERctGtJ3shM+T7I2bPzYgU6FaLzANBgkqhkiG9w0BAQSF
AAOCAQEACxpUAqKxezoZAFrVUFptlB3nMKYaoX3/jYsEmaDGD0eh1qhyZVwL027G
9Vx7VgpiD7CXrK0yh37YF4hZ9qYVM7arPF+SojGgdPVtAQSNAPkb3GkKJtAH8jbH
rv88L97L1Y/gw0oRbgkLPLy5psdHzInb0Q+9TFdgeVVeL9uZXjuF0FFYeSY7z9T7
WmzTdza028qX4lxaKaVkb4wvyN2yfbx82PWzizejZZVw1xuBwLPbA67LLzL7DTb
H+F0mhojB6pOwkl346QLwmcOvFZGV53BTeeBpl/i0iLbpLWVoV0PnDdz1zKuICGZ
V1yv/vTx0A2H/3aXbmZIIIG5TmTfCQ==
-----END CERTIFICATE-----
[analyst@secOps ~]$ openssl x509 -noout -in cisco.pem -fingerprint -sha1
sha1 Fingerprint=E2:D0:0C:87:AF:0D:16:82:B4:45:35:11:DE:37:FD:D0:82:E7:BF:EE
[analyst@secOps ~]$

```

Menu
Terminal

Rainy days ahead  
68°F

Search